UPPER MISSISSIPPI RIVER SYSTEM
ENVIRONMENTAL MANAGEMENT PROGRAM
DEFINITE PROJECT REPORT
WITH INTEGRATED ENVIRONMENTAL ASSESSMENT (R-17PR)
PUBLIC REVIEW DRAFT

RICE LAKE STATE FISH AND WILDLIFE AREA HABITAT REHABILITATION AND ENHANCEMENT PROJECT

LA GRANGE POOL, ILLINOIS WATERWAY
RIVER MILES 132.0 THROUGH 138.0
FULTON COUNTY, ILLINOIS

CONTENTS

Subject **Page**

1. INTRODUCTION 1
A. Purpose. 1
B. Resource Problems and Opportunities. 1
C. Project Selection. 1
D. Scope of Study. 2
E. Format of Report. 2
F. Authority. 2

2. ASSESSMENT OF EXISTING RESOURCES 4
A. Resource History of Study Area 4
B. Discription of Project Area and Current Management. 4
C. Wetland Resources. 4
D. Floodplain Resources 8
E. Aquatic Resources. 8
F. Water Quality. 8
G. Endangered Species. 8
H. Historic Properties. 9
I. Sedimentation. 10
J. Hazardous, Toxic, and Radioactive Waste. 10

3. PROJECT OBJECTIVES 11
A. Problem Identification. 11
B. Resource Significance 12
C. Systemic Habitat Goals (Habitat Needs Assessment) 13
D. General Fish and Wildlife Management Goals for Rice Lake SFWA. 13
E. Project Goals, Objectives, and Potential Enhancement Features. 14
F. Planning Constraints. 15

4. POTENTIAL PROJECT FEATURES 17

A. Potential Features to Restore and Protect Wetland Habitat....17
B. Potential Features to Restore and Protect Aquatic Habitat (Fish Access)....18
C. Potential Features to Restore and Protect Floodplain Habitat 19

5. EVALUATION OF FEASIBLE PROJECT FEATURES AND FORMULATION OF ALTERNATIVES 20
A. Environmental Output Evaluation. 20
B. Feasible Project Features. 20
C. Cost Estimates for Habitat Improvement Measures. 22
D. Incremental Analysis of Project Alternatives 23
E. Selection of Recommended Plan....25

6. RECOMMENDED PLAN: DESCRIPTION WITH DESIGN, CONSTRUCTION, OPERATION, AND MAINTENANCE CONSIDERATIONS....27
A. Perimeter Water Control Levee (L2). 27
B. Pump Station and Conveyance Facilities (P2) 27
C. Fish Access (F2) 28
D. Duck Island Native Vegetation Plantings (T5) 28
E. Project Summary 29
F. Design Considerations....31
G. Operational Considerations....32
H. Maintenance. 32

7. SCHEDULE FOR DESIGN AND CONSTRUCTION 34

8. COST ESTIMATES....35

9. ENVIRONMENTAL EFFECTS 37
A. Summary of Effects 37
B. Economic and Social Impacts....37
C. Natural Resources Impacts. 38
D. Historic Properties....40
E. Mineral Resources 41
F. Farmland Protection....41
G. Cumulative Impacts 42
H. Adverse Impacts Which Cannot Be Avoided 42
I. Short-Term versus Long-Term Productivity 42
J. Irreversible or Irretrievable Resource Commitments 42
K. Relationship of the Proposed Project to Land-Use Plans....42
L. Compliance With Environmental Statutes....42

10. PROJECT PERFORMANCE ASSESSMENT MONITORING....44

11. REAL ESTATE REQUIREMENTS....50

12. IMPLEMENTATION RESPONSIBILITIES AND VIEWS....51
A. Corps of Engineers....51
B. U.S. Fish and Wildlife Service....51
C. Illinois Department of Natural Resources 51

13. COORDINATION, PUBLIC VIEWS, AND COMMENTS....52

A. Coordination Meetings 52
B. Coordination by Correspondence 52

14. CONCLUSIONS 54
15. RECOMMENDATIONS 55

16. FINDING OF NO SIGNIFICANT IMPACT 56

Tables

No.	Title	Page
3-1	Project Goals, Objectives, and Potential Enhancement Features	15
3-2	Development Criteria for Potential Enhancement Features	16
5-1	Environmental Output and Costs of Each Feature	23
5-2	Cost-Effective Alternative Combinations	24
5-3	"Best Buys" of Cost-Effective Alternative Combinations	25
6-1	Rice Lake HREP Feature Summary	29
6-2	Rice Lake HREP Probable Construction Sequence	32
7-1	Project Implementation Schedule	34
8-1	Project Design and Construction Cost Estimates	35
8-2	Estimated Annual Operation and Maintenance Costs (April 2004 Price Level)	36
8-3	Estimated Post-Construction Annual Monitoring Costs (April 2004 Price Level)	37
9-1	Relationship of Plans to Environmental Protection Statutes and Other Environmental Requirements	43
10-1	Monitoring and Performance Evaluation Matrix	45
10-2	Resource Monitoring and Data Collection Summary	46
10-3	Post-Construction Evaluation Plan	48

Figures

No.	Title	Page
ES-1	Project Location Map	ES-4
2-1	2000 IWW LaGrange Pool Rice Lake HREP Landcover Map	7

Plates

No.	Title
1	Location and Vicinity Maps
2	Index and General Notes
3	Existing Conditions Site Plan
4	Project Enhancement Features Evaluated
5	Project Enhancement Features Not Evaluated
6	Recommended Plan
7	Perimeter Water Control Levee Plan
8	Perimeter Water Control Levee, Plan and Profile Sta. 0+00 to Sta. 25+00

9 Perimeter Water Control Levee, Plan and Profile Sta. 25+00 to Sta. 50+00
10 Perimeter Water Control Levee, Plan and Profile Sta. 50+00 to Sta. 75+00
11 Perimeter Water Control Levee, Plan and Profile Sta. 75+00 to Sta. 100+00
12 Perimeter Water Control Levee, Plan and Profile Sta. 100+00 to Sta. 125+00
13 Perimeter Water Control Levee, Plan and Profile Sta. 125+00 to Sta. 150+33
14 Perimeter Water Control Levee Typical Sections
15 Gatewell Structure Plan and Section
16 Fish Egress Structure Plan
17 Fish Egress Structure Section
18 Pump Station Discharge Channel Plan
19 Typical Discharge Channel Plan
20 Water Control Structure Voorhees Unit Plan and Section
21 Water Control Structure Big Lake Plan and Section
22 Water Control Structure Rice Lake Plan and Section
23 Water Control Structure Lower Slim Lake Plan and Section
24 Water Control Structure Upper Slim Lake Plan and Section
25 Pump Station Site Plan
26 Pump Station Elevation and Details
27 Pump Station Bulkhead Details
28 Boring Locations
29 Boring Logs I
30 Boring Logs II
31 Boring Logs III
32 Post Construction Monitoring Plan

Appendices

A - Correspondence
B - Clean Water Act, Section 404(b)(1) Evaluation
C - Draft Project Cooperation Agreement
D - Habitat Evaluation and Quantification
E - Geotechnical Considerations
F - Water Quality
G - Hydrology and Hydraulics
H - Structural Considerations
I - Mechanical/Electrical
J - Cost Estimate
K - Literature Cited
L - Real Estate Plan
M – Hazardous, Toxic, and Radioactive Waste
N - Distribution List