300 0 300 600 900

Scale 1" = 300'

Dual-Transducer Survey with 200 Foot Interval Coverage

Channel Contour Color Fill Legend

-10' - -1' | 0' - 8' | 9' | 10' | 10.5 | 11' - 19' | 12 | 20' - 29' | 30' - 50'

Location	Stage		Flat Pool
Morris	4.3	=	482.8
LaSalle	10.2	=	440.2
Peoria	11.6	=	440.0
Havana	4.8	=	429.2
Beardstown	9.1	=	429.0

Hydrographic Survey of the **Illinois Waterway** Ortho photography flown 1995

Horizontal Projection: State Plane, NAD1983, Illinois West - 1202 U.S. Survey Feet

Vertical Datum: NGVD 1929 U.S. Survey Feet. All soundings adjusted to Flat Pool: 429.9

Water Surface at time of survey: 448.4 / Water Stage: +18.5 Feet

Survey Vessel: MV Holling

Conducted by: Justin Coldwater and Lee Schweiger

Processed in Autodesk LDDT by: Bob Adams on 18 May 2011

File Name: IWW_LA_1510-1525_11A.dwg

US ARMY CORPS OF ENGINEERS
MVR-ROCK ISLAND DISTRICT
OPERATIONS DIVISION - TECH SUPPORT BRANCH

Pekin Bend to Pekin

Survey Date: 4 May 2011

IWW / LaGrange Pool - Reach River Miles: 151.0 - 152.5

I/LA